

Civil Engineering

Land Planning

Hydrology/ Flood Control

Geotechnical Engineering

Public Works Services

Storm Water Management



2340 Palma Drive, Suite 200  
Ventura, California 93003  
p: 805.485.3935

San Luis Obispo p: 805.596.0216

[www.rjreng.com](http://www.rjreng.com)

**FEASIBILITY HYDRAULIC CALCULATIONS  
2525 E. HILLCREST DRIVE  
THOUSAND OAKS, CALIFORNIA**

Prepared For:

**CONEJO VALLEY CHURCH OF CHRIST**  
2525 E. Hillcrest Drive  
Thousand Oaks, California 91362

Date: June 8, 2018

Project: 6014.60

A handwritten signature in blue ink, appearing to be 'R. Anderson', written over a horizontal line.

Approved: \_\_\_\_\_

Robert W. Anderson, PE, JD, CPESC, CPSWQ, CMS4S, CESSWI  
RCE 58383, Exp. 12-31-18

**HYDRAULIC ANALYSIS  
CONEJO VALLEY CHURCH OF CHRIST  
2525 E. HILLCREST DRIVE  
THOUSAND OAKS, CALIFORNIA**

---

**EXECUTIVE SUMMARY**

RJR Engineering Group (RJR) has prepared this Hydraulic Analysis regarding the proposed Storm Drain Improvements for Conejo Valley Church of Christ located at 2525 E. Hillcrest Drive in Thousand Oaks.

The scope of this analysis is to characterize the hydrologic and hydraulic conditions of the onsite drainage scheme and any impact on the existing Storm Drain System located on E Hillcrest Drive.

In anticipation of street resurfacing by The City of Thousand Oaks starting on July 1, 2018, the proposed storm drain junction structure for the proposed project, which occurs within the Hillcrest Drive right of way, will be constructed ahead of the proposed site improvement. A preliminary storm drain system has been designed and modeled to ensure functionality, but at this time only the street connection will be constructed. The proposed site improvements will consist of the construction of a junction structure on the existing 39" RCP Storm Drain Main Line located under E. Hillcrest Drive. A 36" RCP service line will be joined and extended to 35 feet past the right of way, onto the property, and capped until the final design can be constructed in the near future.

The proposed storm water facilities and improvements have all been designed for the interception and conveyance of the surface water runoff for a 25 year storm event in accordance with the City of Thousand Oaks requirements. Hydrology flow rates from the City of Thousand Oaks Master Drainage Plan were utilized in the hydraulic analysis.

It should be noted that this report has been prepared solely as a hydrologic and hydraulic analysis for the proposed site and drainage improvements. This analysis pertains solely to the conveyance of surface water, the related drainage devices and the storm water management system and does not include any assumptions relating to downstream conditions. All recommendations described herein are based on hydraulic and hydrologic analysis. Any changes in design or failure to address the outlined recommendations can alter the subsequent calculations and render this report void.



## **1.0. HYDRAULIC ANALYSIS**

### **Storm Drain Facility Design**

One dimensional supportive calculations for the existing storm drain system with the addition of the proposed system are included in Appendix A. All the drainage structures have been sufficiently designed to convey the  $Q_{25}$  flows to the corresponding inlet structures.

The Hydrology Map in Appendix B illustrates the total drainage area and the corresponding flow rates ( $Q$ 's) for the specific conditions and flood frequencies, as well as the proposed catch basins, v-ditches, pipes, detention basin locations and any other relevant information.

### **Hydraulic Modeling**

Specifics from City Storm Drain As-Built Drawing Number 85-43A were incorporated into the hydraulic model. Flow rate values from the As-Builts were modeled in AutoDesk Storm Sewer Software to produce flow velocities and hydraulic grade lines to ensure the existing storm drain has the capacity to convey the proposed flow rate. Rain fall run off values from the City of Thousand Oaks Master Drainage Plan were also utilized to model the hydraulic capacity of the proposed configuration. The results from both modeling scenarios for the 10-year and 25-year storm are attached in Appendix A.

## **2.0. CONCLUSION**

Based on the available data and analysis, it is of the opinion of RJR that the proposed storm drain system is hydraulically adequate to provide the necessary conveyance of water of the 25 year storm event.

Again, it should be noted that this report has been prepared solely as a surficial hydrology and hydraulic analysis for the grading and drainage improvements. The hydrology and hydraulic calculations are based on the survey provided, visual field measurements, civil plans designed by RJR, and the architectural and landscape structures designed by others. All recommendations described herein are based on hydraulic analysis associated with the above referenced grading and drainage design, and any changes in design or failure to address the outlined recommendations can alter the subsequent calculations and render this report void.



## REFERENCES

1. Ventura County Watershed Protection District, Hydrology Manual, December 2010.
2. City of Thousand Oaks Drawing Number 85-43A
3. City of Thousand Oaks Storm Drain System Master Plan, Hydrology Plate #6



## **APPENDIX A**

### **Calculations**

- 1. Master Plan 25-year Hydraulic Analysis**
- 2. Master Plan 10-year Hydraulic Analysis**
- 3. As-Built Plan 25-year Hydraulic Analysis**
- 4. As-Built Plan 10-year Hydraulic Analysis**

**EXHIBIT 21. DESIGN STORM RATIOS**


Category (1)	2-yr	5-yr	10-yr	25-yr	50-yr	100-yr	200-yr	500-yr
* Precipitation	0.43	0.61	0.73	0.88	1.00	1.11	Not Analyzed	Not Analyzed
Undeveloped-HMS & HSPF	0.043	0.144	0.262	0.484	0.711	1.000	1.345	1.952
Developed HMS & HSPF	0.166	0.330	0.464	0.660	0.882	1.000	1.191	1.502
Undeveloped-VCRat (2)	0.043	0.144	0.362	0.484	0.711	1.000	1.345	1.952
Developed VCRat (2)	0.166	0.330	0.567	0.660	0.882	1.000	1.191	1.502
Casitas Dam Outflow	0.005	0.030	0.048	0.110	0.143	1.000	1.191	1.448
Coyote Ck below Dam	0.005	0.100	0.200	0.400	0.580	1.000	1.191	1.416
Piru Ck Below Dam	0.031	0.042	0.061	0.136	0.805	1.000	1.183	1.463

Note (1): Ratios cannot be used for watersheds with detention basins or water storage dams affecting more than 10% of the area except for those developed specifically for dam outflow (Casitas and Piru).

Note (2): VCRat ratios provided for reference only as current practice is to run the model using the correct Tc's and rainfall for all storms required for design studies. In rare cases it may be necessary to use the multipliers in VCRat studies such as estimating 10-yr peaks from Soil Type 7 in the J' zone.




# Church Q25 w Q25 MP





# Storm Sewer Profile

Proj. file: Church Q25 with 39in Q25 MP Junction Analysis.stm



Line No.	Area Dn (sqft)	Area Up (sqft)	Byp Ln No	Coeff C1 (C)	Coeff C2 (C)	Coeff C3 (C)	Capac Full (cfs)	Crit Depth (ft)	Cross SI, Sw (ft/ft)	Cross SI, Sx (ft/ft)	Curb Len (ft)	Defl Ang (Deg)	Depth Dn (ft)	Depth Up (ft)	DnStm Ln No	Dmg Area (ac)	Easting X (ft)	EGL Dn (ft)	EGL Up (ft)	Energy Loss (ft)
1	8.29	8.30	n/a	0.20	0.50	0.90	126.62	3.23	...	...	...	58.922	3.25	3.25	Outfall	0.00	4267.85	901.03	912.16	11.136
* 2	7.07	7.07	n/a	0.20	0.50	0.90	120.65	2.03	...	...	...	-32.094	3.00	3.00	1	0.00	4276.17	909.54	909.56	0.027
3	7.07	7.07	n/a	0.20	0.50	0.90	164.61	2.03	...	...	...	-29.679	3.00	3.00	2	0.00	4304.65	909.82	909.91	0.083
4	5.09	5.11	n/a	0.20	0.50	0.90	228.56	2.03	...	...	...	-28.374	3.00	2.04**	3	0.00	4393.09	910.16	910.57	0.384
5	5.09	5.09	n/a	0.20	0.50	0.90	228.08	2.03	...	...	...	3.583	2.17	2.03**	4	0.00	4414.96	910.72	913.03	0.000
6	5.09	5.09	n/a	0.20	0.50	0.90	250.32	2.03	...	...	...	3.583	2.03	2.03**	5	0.00	4519.11	913.03	926.72	0.000
7	5.09	5.09	n/a	0.20	0.50	0.90	251.49	2.03	...	...	...	13.875	2.03	2.03**	6	0.00	4541.53	926.72	929.48	0.000
8	5.09	5.09	n/a	0.20	0.50	0.90	260.57	2.03	...	...	...	13.875	2.03	2.03**	7	0.00	4678.94	929.48	947.39	0.000
9	5.09	5.09	n/a	0.20	0.50	0.90	162.48	2.03	...	...	...	-12.176	2.03	2.03**	8	0.00	4691.46	947.39	948.03	0.000
10	5.09	5.09	n/a	0.20	0.50	0.90	161.44	2.03	...	...	...	-15.089	2.03	2.03**	9	0.00	4774.99	948.03	952.58	0.000
11	5.09	5.09	n/a	0.20	0.50	0.90	161.77	2.03	...	...	...	0.000	2.03	2.03**	10	0.00	4821.98	952.58	955.15	0.000
12	5.09	5.09	n/a	0.20	0.50	0.90	161.50	2.03	...	...	...	-7.823	2.03	2.03**	11	0.00	4845.21	955.15	956.51	0.000
13	5.09	5.09	n/a	0.20	0.50	0.90	569.08	2.03	...	...	...	-9.560	2.03	2.03**	12	0.00	4859.12	956.51	967.94	0.000
* 14	8.29	8.30	1	0.20	0.50	0.90	136.88	3.19	...	...	...	-1.589	3.25	3.25	1	0.00	4384.94	913.75	919.37	5.624

\* Line 2 & 14 Form Junction

Church Q25 w Q25 MP Date: 6/8/2018

Number of lines: 14

NOTES: \*\* Critical depth

Flow Rate (cfs)	Sf Ave (ft/ft)	Sf Dn (ft/ft)	Grate Area (sqft)	Grate Len (ft)	Grate Width (ft)	Gnd/Rim El Dn (ft)	Gnd/Rim El Up (ft)	Gutter Depth (ft)	Gutter Slope (ft/ft)	Gutter Spread (ft)	Gutter Width (ft)	HGL Dn (ft)	HGL Up (ft)	HGL Jnct (ft)	HGL Jmp Dn (ft)	HGL Jmp Up (ft)	Incr CxA	Incr Q (cfs)	Inlet Depth (ft)
183.00	4.914	4.915	...	...	...	0.00	907.64	...	...	...	...	893.46	904.60	909.06	...	...	0.00	0.00	...
39.00	0.291	0.291	...	...	...	907.64	899.06	...	...	...	...	909.06	909.09	909.35	...	...	0.00	0.00	...
39.00	0.291	0.291	...	...	...	899.06	900.54	...	...	...	...	909.35	909.43	909.68	...	...	0.00	0.00	...
39.00	0.371	0.291	...	...	...	900.54	910.89	...	...	...	...	909.68	909.67	909.80	...	...	0.00	0.00	...
39.00	0.000	0.000	...	...	...	910.89	913.35	...	...	...	...	909.80	912.12 j	912.12	909.91	910.51	0.00	0.00	...
39.00	0.000	0.000	...	...	...	913.35	927.04	...	...	...	...	912.12	925.81	925.81	...	...	0.00	0.00	...
39.00	0.000	0.000	...	...	...	927.04	929.80	...	...	...	...	925.81	928.57	928.57	...	...	0.00	0.00	...
39.00	0.000	0.000	...	...	...	929.80	947.71	...	...	...	...	928.57	946.48	946.48	...	...	0.00	0.00	...
39.00	0.000	0.000	...	...	...	947.71	948.34	...	...	...	...	946.48	947.12	947.12	...	...	0.00	0.00	...
39.00	0.000	0.000	...	...	...	948.34	952.90	...	...	...	...	947.12	951.67	951.67	...	...	0.00	0.00	...
39.00	0.000	0.000	...	...	...	952.90	955.47	...	...	...	...	951.67	954.24	954.24	...	...	0.00	0.00	...
39.00	0.000	0.000	...	...	...	955.47	956.83	...	...	...	...	954.24	955.60	955.60	...	...	0.00	0.00	...
39.00	0.000	0.000	...	...	...	956.83	969.10	...	...	...	...	955.60	967.03	967.03	...	...	0.00	39.00	...
144.00	2.592	2.593	...	...	...	907.64	0.00	...	...	...	...	909.06	914.69	919.37	...	...	0.00	144.00	...

Church Q25 w Q25 MP

Number of lines: 14

Date: 6/8/2018

NOTES: \*\* Critical depth

Inlet Eff (%)	Inlet ID	Inlet Loc	Inlet Time (min)	i Sys (in/hr)	i Inlet (in/hr)	Invert Dn (ft)	Invert Up (ft)	Jump Loc (ft)	Jump Len (ft)	Vel Hd Jump Dn (ft)	Vel Hd Jump Up (ft)	J-Loss Coeff	Junct Type	Known Q (cfs)	Cost RCP	Cost CMP	Cost PVC
...	Structure - (706)	On Grade	0.0	0.00	0.00	890.21	895.54	...	...	0.00	0.00	0.59	MH	0.00	160	144	136
...	Structure - (705)	On Grade	0.0	0.00	0.00	895.54	895.80	...	...	0.00	0.00	0.55	None	0.00	660	594	561
...	Structure - (704)	On Grade	0.0	0.00	0.00	895.80	897.28	...	...	0.00	0.00	0.53	None	0.00	1,354	1,219	1,151
...	Structure - (703)	On Grade	0.0	0.00	0.00	897.28	907.63	...	...	0.00	0.00	0.15	None	0.00	4,632	4,169	3,937
...	Structure - (702)	On Grade	0.0	0.00	0.00	907.63	910.09	2.47	10.15	0.91	1.54	0.15 z	None	0.00	1,178	1,060	1,001
...	Structure - (701)	On Grade	0.0	0.00	0.00	910.09	923.78	...	...	0.00	0.00	0.28 z	None	0.00	5,116	4,604	4,349
...	Structure - (700)	On Grade	0.0	0.00	0.00	923.78	926.54	...	...	0.00	0.00	0.28 z	None	0.00	1,090	981	927
...	Structure - (699)	On Grade	0.0	0.00	0.00	926.54	944.45	...	...	0.00	0.00	0.25 z	None	0.00	6,150	5,535	5,228
...	Structure - (698)	On Grade	0.0	0.00	0.00	944.45	945.09	...	...	0.00	0.00	0.31 z	None	0.00	650	565	553
...	Structure - (697)	On Grade	0.0	0.00	0.00	945.09	949.64	...	...	0.00	0.00	0.15 z	None	0.00	4,104	3,694	3,488
...	Structure - (696)	On Grade	0.0	0.00	0.00	949.64	952.21	...	...	0.00	0.00	0.17 z	None	0.00	2,344	2,110	1,992
...	Structure - (695)	On Grade	0.0	0.00	0.00	952.21	953.57	...	...	0.00	0.00	0.20 z	None	0.00	1,288	1,159	1,095
...	Structure - (694)	On Grade	0.0	0.00	0.00	953.57	965.00	...	...	0.00	0.00	1.00 z	MH	39.00	928	835	789
...		Sag	0.0	0.00	0.00	895.54	900.62	...	...	0.00	0.00	1.00	MH	144.00	100	90	85

Church Q25 w Q25 MP

Number of lines: 14

Date: 6/8/2018

NOTES: Intensity = 102.61 / (Inlet time + 16.50) ^ 0.82 --- Return period = 25 Yrs. ; \*\* Critical depth

Line ID	Line Length (ft)	Line Size (in)	Line Slope (%)	Line Type	Local Depr (in)	n-val Gutter	n-val Pipe	Minor Loss (ft)	Northing Y (ft)	Pipe Travel (min)	Q Byp (cfs)	Q Capt (cfs)	Q Carry (cfs)	Line Rise (in)	Runoff Coeff (C)	Line Span (in)	Area A1 (ac)	Area A2 (ac)	Area A3 (ac)	Tc (min)	Throat Ht (in)
Pipe - (697)	226.620	39	2.35	Cir	...	...	0.013	4.46	4811.37	0.17	...	...	...	39	0.00	39	0.00	0.00	0.00	1.9	...
* Pipe - (695)	9.325	36	2.79	Cir	...	...	0.012	0.26	4807.16	0.03	...	...	...	36	0.00	36	0.00	0.00	0.00	1.9	...
Pipe - (694)	28.513	36	5.19	Cir	...	...	0.012	0.25	4808.58	0.09	...	...	...	36	0.00	36	0.00	0.00	0.00	1.8	...
Pipe - (693)	103.428	36	10.01	Cir	...	...	0.012	0.14	4862.20	0.31	...	...	...	36	0.00	36	0.00	0.00	0.00	1.5	...
Pipe - (692)	24.686	36	9.97	Cir	...	...	0.012	n/a	4873.65	0.07	...	...	...	36	0.00	36	0.00	0.00	0.00	1.4	...
Pipe - (691)	114.056	36	12.00	Cir	...	...	0.012	0.26	4920.15	0.34	...	...	...	36	0.00	36	0.00	0.00	0.00	1.1	...
Pipe - (690)	22.781	36	12.12	Cir	...	...	0.012	0.26	4924.17	0.07	...	...	...	36	0.00	36	0.00	0.00	0.00	1.0	...
Pipe - (689)	137.700	36	13.01	Cir	...	...	0.012	0.23	4915.31	0.42	...	...	...	36	0.00	36	0.00	0.00	0.00	0.6	...
Pipe - (688)	12.655	36	5.06	Cir	...	...	0.012	0.28	4917.18	0.04	...	...	...	36	0.00	36	0.00	0.00	0.00	0.6	...
Pipe - (687)	91.135	36	4.99	Cir	...	...	0.012	0.14	4953.63	0.28	...	...	...	36	0.00	36	0.00	0.00	0.00	0.3	...
Pipe - (686)	51.266	36	5.01	Cir	...	...	0.012	0.16	4974.13	0.15	...	...	...	36	0.00	36	0.00	0.00	0.00	0.1	...
Pipe - (685)	27.218	36	5.00	Cir	...	...	0.012	0.18	4988.31	0.08	...	...	...	36	0.00	36	0.00	0.00	0.00	0.1	...
Pipe - (684)	18.424	36	62.04	Cir	...	...	0.012	0.91	5000.39	0.06	...	...	...	36	0.00	36	0.00	0.00	0.00	0.0	...
* 216.927		39	2.34	Cir	...	...	0.012	4.68	4628.75	0.21	...	...	...	39	0.00	39	0.00	0.00	0.00	0.0	...

Church Q25 w Q25 MP

Number of lines: 14

Date: 6/8/2018

NOTES: \*\* Critical depth

Total Area (ac)	Total CxA	Total Runoff (cfs)	Vel Ave (ft/s)	Vel Dn (ft/s)	Vel Hd Dn (ft)	Vel Hd Up (ft)	Vel Up (ft/s)	Cover Dn (ft)	Cover Up (ft)	Storage (cft)
0.00	0.00	0.00	22.06	22.06	7.57	7.57	22.06	n/a	8.85	1879.62
0.00	0.00	0.00	5.52	5.52	0.47	0.47	5.52	9.10	0.26	65.90
0.00	0.00	0.00	5.52	5.52	0.47	0.47	5.52	0.26	0.26	201.51
0.00	0.00	0.00	6.57	5.52	0.47	0.90	7.63	0.26	0.26	697.22
0.00	0.00	0.00	7.38	7.11	0.91	0.91	7.66	0.26	0.26	130.59
0.00	0.00	0.00	7.66	7.66	0.91	0.91	7.66	0.26	0.26	580.83
0.00	0.00	0.00	7.66	7.66	0.91	0.91	7.66	0.26	0.26	116.01
0.00	0.00	0.00	7.66	7.66	0.91	0.91	7.66	0.26	0.26	701.24
0.00	0.00	0.00	7.66	7.66	0.91	0.91	7.66	0.26	0.25	64.45
0.00	0.00	0.00	7.66	7.66	0.91	0.91	7.66	0.25	0.26	464.11
0.00	0.00	0.00	7.66	7.66	0.91	0.91	7.66	0.26	0.26	261.07
0.00	0.00	0.00	7.66	7.66	0.91	0.91	7.66	0.26	0.26	138.61
0.00	0.00	0.00	7.66	7.66	0.91	0.91	7.66	0.26	1.10	93.82
0.00	0.00	0.00	17.36	17.36	4.69	4.68	17.36	8.85	n/a	1799.22

Church Q25 w Q25 MP		Number of lines: 14	Date: 6/8/2018
NOTES: ** Critical depth			

# Hydraulic Grade Line Computations

Line Size (in)	Q (cfs)	Downstream								Len (ft)	Upstream						Check		JL coeff (K)	Minor loss (ft)
		Invert elev (ft)	HGL elev (ft)	Depth (ft)	Area (sqft)	Vel (ft/s)	Vel head (ft)	EGL elev (ft)	Sf (%)		Invert elev (ft)	HGL elev (ft)	Depth (ft)	Area (sqft)	Vel (ft/s)	Vel head (ft)	EGL elev (ft)	Sf (%)		
1	183.0	890.21	893.46	3.25	8.29	22.06	7.57	901.03	4.915	226.62	3.25	8.30	22.06	7.57	912.16	4.913	4.914	11.14	0.59	4.46
2	39.00	895.54	909.06	3.00	7.07	5.52	0.47	909.54	0.291	9.325	3.00	7.07	5.52	0.47	909.56	0.291	0.291	0.027	0.55	0.26
3	39.00	895.80	909.35	3.00	7.07	5.52	0.47	909.82	0.291	28.513	3.00	7.07	5.52	0.47	909.91	0.291	0.291	0.083	0.53	0.25
4	39.00	897.28	909.68	3.00	5.09	5.52	0.47	910.16	0.291	103.42	2.04**	5.11	7.63	0.90	910.57	0.450	0.371	0.384	0.15	0.14
5	39.00	907.63	909.80	2.17	5.09	7.11	0.91	910.72	0.000	24.686	2.03**	5.09	7.66	0.91	913.03	0.000	0.000	n/a	0.15	0.14
6	39.00	910.09	912.12	2.03*	5.09	7.66	0.91	913.03	0.000	114.05	2.03**	5.09	7.66	0.91	926.72	0.000	0.000	n/a	0.28	0.26
7	39.00	923.78	925.81	2.03*	5.09	7.66	0.91	926.72	0.000	22.781	2.03**	5.09	7.66	0.91	929.48	0.000	0.000	n/a	0.28	0.26
8	39.00	926.54	928.57	2.03*	5.09	7.66	0.91	929.48	0.000	137.70	2.03**	5.09	7.66	0.91	947.39	0.000	0.000	n/a	0.25	0.23
9	39.00	944.45	946.48	2.03*	5.09	7.66	0.91	947.39	0.000	12.655	2.03**	5.09	7.66	0.91	948.03	0.000	0.000	n/a	0.31	0.28
10	39.00	945.09	947.12	2.03*	5.09	7.66	0.91	948.03	0.000	91.135	2.03**	5.09	7.66	0.91	952.58	0.000	0.000	n/a	0.15	0.14
11	39.00	949.64	951.67	2.03*	5.09	7.66	0.91	952.58	0.000	51.266	2.03**	5.09	7.66	0.91	955.15	0.000	0.000	n/a	0.17	0.16
12	39.00	952.21	954.24	2.03*	5.09	7.66	0.91	955.15	0.000	27.218	2.03**	5.09	7.66	0.91	956.51	0.000	0.000	n/a	0.20	0.18
13	39.00	953.57	955.60	2.03*	5.09	7.66	0.91	956.51	0.000	18.424	2.03**	5.09	7.66	0.91	967.94	0.000	0.000	n/a	1.00	0.91
14	144.0	895.54	909.06	3.25	8.29	17.36	4.69	913.75	2.593	216.92	3.25	8.30	17.36	4.68	919.37	2.592	2.592	5.624	1.00	4.68

Church Q25 w Q25 MP

Number of lines: 14


Run Date: 6/8/2018

Notes: \* depth assumed; \*\* Critical depth.; j-Line contains hyd. jump ; c = cir e = ellip b = box






# Church Q25 w Q25 MP



# Storm Sewer Profile

Proj. file: Church Q25 with 39in Q25 MP.stm



# Storm Sewer Summary Report

Line No.	Line ID	Flow rate (cfs)	Line Size (in)	Line shape	Line length (ft)	Invert EL Dn (ft)	Invert EL Up (ft)	Line Slope (%)	HGL Down (ft)	HGL Up (ft)	Minor loss (ft)	HGL Junct (ft)	Dns Line No.	Junction Type
1	Pipe - (697)	183.0	39	Cir	226.620	890.21	895.54	2.352	893.44*	904.23*	4.46	908.70	End	Manhole
2	Pipe - (695)	39.00	36	Cir	9.325	895.54	895.80	2.788	908.70*	908.72*	0.26	908.98	1	None
3	Pipe - (694)	39.00	36	Cir	28.513	895.80	897.28	5.191	908.98*	909.07*	0.25	909.32	2	None
4	Pipe - (693)	39.00	36	Cir	103.428	897.28	907.63	10.007	909.32	909.66	0.14	909.66	3	None
5	Pipe - (692)	39.00	36	Cir	24.686	907.63	910.09	9.965	909.66	912.12	0.14	912.12	4	None
6	Pipe - (691)	39.00	36	Cir	114.056	910.09	923.78	12.003	912.12	925.81	0.26	925.81	5	None
7	Pipe - (690)	39.00	36	Cir	22.781	923.78	926.54	12.115	925.81	928.57	0.26	928.57	6	None
8	Pipe - (689)	39.00	36	Cir	137.700	926.54	944.45	13.007	928.57	946.48	0.23	946.48	7	None
9	Pipe - (688)	39.00	36	Cir	12.655	944.45	945.09	5.057	946.48	947.12	0.28	947.12	8	None
10	Pipe - (687)	39.00	36	Cir	91.135	945.09	949.64	4.993	947.12	951.67	0.14	951.67	9	None
11	Pipe - (686)	39.00	36	Cir	51.266	949.64	952.21	5.013	951.67	954.24	0.16	954.24	10	None
12	Pipe - (685)	39.00	36	Cir	27.218	952.21	953.57	4.997	954.24	955.60	0.18	955.60	11	None
13	Pipe - (684)	39.00	36	Cir	18.424	953.57	965.00	62.038	955.60	967.03	0.91	967.03	12	Manhole

Church Q25 w Q25 MP Number of lines: 13 Run Date: 6/8/2018

NOTES: Return period = 25 Yrs. ; \*Surcharged (HGL above crown).

# Hydraulic Grade Line Computations

Line Size (in)	Q (cfs)	Downstream						Len (ft)	Upstream						Check		JL coeff (K)	Minor loss (ft)					
		Invert elev (ft)	HGL elev (ft)	Depth (ft)	Area (sqft)	Vel (ft/s)	Vel head (ft)		EGL elev (ft)	Sf (%)	Invert elev (ft)	HGL elev (ft)	Depth (ft)	Area (sqft)	Vel (ft/s)	Vel head (ft)			EGL elev (ft)	Sf (%)	Ave Sf (%)	Enrgy loss (ft)	
1	39	183.0	890.21	893.44	3.23	8.29	22.08	7.58	901.02	4.600	226.62	895.54	904.23	3.25	8.30	22.06	7.57	911.80	4.913	4.757	10.78	0.59	4.46
2	36	39.00	895.54	908.70	3.00	7.07	5.52	0.47	909.17	0.291	9.325	895.80	908.72	3.00	7.07	5.52	0.47	909.20	0.291	0.291	0.027	0.55	0.26
3	36	39.00	895.80	908.98	3.00	7.07	5.52	0.47	909.46	0.291	28.513	897.28	909.07	3.00	7.07	5.52	0.47	909.54	0.291	0.291	0.083	0.53	0.25
4	36	39.00	897.28	909.32	3.00	5.09	5.52	0.47	909.79	0.291	103.42	8907.63	909.66	2.03**	5.09	7.66	0.91	910.57	0.455	0.373	n/a	0.15	0.14
5	36	39.00	907.63	909.66	2.03*	5.09	7.66	0.91	910.57	0.000	24.686	910.09	912.12	2.03**	5.09	7.66	0.91	913.03	0.000	0.000	n/a	0.15	0.14
6	36	39.00	910.09	912.12	2.03*	5.09	7.66	0.91	913.03	0.000	114.05	8923.78	925.81	2.03**	5.09	7.66	0.91	926.72	0.000	0.000	n/a	0.28	0.26
7	36	39.00	923.78	925.81	2.03*	5.09	7.66	0.91	926.72	0.000	22.781	926.54	928.57	2.03**	5.09	7.66	0.91	929.48	0.000	0.000	n/a	0.28	0.26
8	36	39.00	926.54	928.57	2.03*	5.09	7.66	0.91	929.48	0.000	137.70	944.45	946.48	2.03**	5.09	7.66	0.91	947.39	0.000	0.000	n/a	0.25	0.23
9	36	39.00	944.45	946.48	2.03*	5.09	7.66	0.91	947.39	0.000	12.655	945.09	947.12	2.03**	5.09	7.66	0.91	948.03	0.000	0.000	n/a	0.31	0.28
10	36	39.00	945.09	947.12	2.03*	5.09	7.66	0.91	948.03	0.000	91.135	949.64	951.67	2.03**	5.09	7.66	0.91	952.58	0.000	0.000	n/a	0.15	0.14
11	36	39.00	949.64	951.67	2.03*	5.09	7.66	0.91	952.58	0.000	51.266	952.21	954.24	2.03**	5.09	7.66	0.91	955.15	0.000	0.000	n/a	0.17	0.16
12	36	39.00	952.21	954.24	2.03*	5.09	7.66	0.91	955.15	0.000	27.218	953.57	955.60	2.03**	5.09	7.66	0.91	956.51	0.000	0.000	n/a	0.20	0.18
13	36	39.00	953.57	955.60	2.03*	5.09	7.66	0.91	956.51	0.000	18.424	965.00	967.03	2.03**	5.09	7.66	0.91	967.94	0.000	0.000	n/a	1.00	0.91

Church Q25 w Q25 MP


Number of lines: 13

Run Date: 6/8/2018

Notes: \* depth assumed; \*\* Critical depth. ; c = cir e = ellip b = box



# Hillcrest Q25 MP




Project File: Existing 39in Hillcrest Q25 MP with Church Q25.stm

Number of lines: 3

Date: 5/16/2018

# Storm Sewer Profile

Proj. file: Existing 39in Hillcrest Q25 MP with Church Q25.stm



# Storm Sewer Summary Report

Line No.	Line ID	Flow rate (cfs)	Line Size (in)	Line shape	Line length (ft)	Invert EL Dn (ft)	Invert EL Up (ft)	Line Slope (%)	HGL Down (ft)	HGL Up (ft)	Minor loss (ft)	HGL Junct (ft)	Dns Line No.	Junction Type	
1	Pipe - (697)	183.0	39	Cir	226.620	890.21	895.54	2.352	893.44*	904.21*	1.13	905.34	End	Manhole	
2	Pipe - (695) (1) (1)	144.0	39	Cir	39.579	895.54	895.86	0.809	905.34*	906.37*	0.70	907.07	1	Manhole	
3	Pipe - (695) (1)	144.0	39	Cir	129.740	895.86	896.89	0.794	907.07*	910.44*	4.68	915.12	2	None	
Project File: Existing 39in Hillicrest Q25 MP with Church Q25.stm													Number of lines: 3		Run Date: 5/18/2018
NOTES: Return period = 25 Yrs. ; *Surcharged (HGL above crown).															



# Hydraulic Grade Line Computations


Line Size (in)	Q (cfs)	Downstream						Len (ft)	Upstream						Check		JL coeff (K)	Minor loss (ft)				
		Invert elev (ft)	HGL elev (ft)	Depth (ft)	Area (sqft)	Vel (ft/s)	Vel head (ft)		EGL elev (ft)	Sf (%)	Invert elev (ft)	HGL elev (ft)	Depth (ft)	Area (sqft)	Vel (ft/s)	Vel head (ft)			EGL elev (ft)	Sf (%)	Ave Sf (%)	Energy loss (ft)
1	183.0	890.21	893.44	3.23	8.29	22.08	7.58	901.02	4.578	226.62	895.54	904.21	3.25	8.30	22.06	7.57	911.77	4.913	4.745	10.75	0.15	1.13
2	144.0	895.54	905.34	3.25	8.29	17.36	4.69	910.03	2.593	39.579	895.86	906.37	3.25	8.30	17.36	4.68	911.05	2.592	2.592	1.026	0.15	0.70
3	144.0	895.86	907.07	3.25	8.29	17.36	4.69	911.76	2.593	129.74	896.89	910.44	3.25	8.30	17.36	4.68	915.12	2.592	2.592	3.363	1.00	4.68

Project File: Existing 39in Hillcrest Q25 MP with Church Q25.stm

Number of lines: 3 Run Date: 5/18/2018

; c = cir e = ellip b = box

# Church Q25 w Q25 MP




Project File: Church Q25 with 39in Q25 MP.stm

Number of lines: 13

Date: 5/16/2018

# Storm Sewer Profile

Proj. file: Church Q25 with 39in Q25 MP.stm



# Storm Sewer Summary Report


Line No.	Line ID	Flow rate (cfs)	Line Size (in)	Line shape	Line length (ft)	Invert EL Dn (ft)	Invert EL Up (ft)	Line Slope (%)	HGL Down (ft)	HGL Up (ft)	Minor loss (ft)	HGL Junct (ft)	Dns Line No.	Junction Type
1	Pipe - (697)	183.0	39	Cir	226.620	890.21	895.54	2.352	893.44*	904.23*	4.46	908.70	End	Manhole
2	Pipe - (695)	39.00	36	Cir	9.325	895.54	895.80	2.788	908.70*	908.72*	0.26	908.98	1	None
3	Pipe - (694)	39.00	36	Cir	28.513	895.80	897.28	5.191	908.98*	909.07*	0.25	909.32	2	None
4	Pipe - (693)	39.00	36	Cir	103.428	897.28	907.63	10.007	909.32	909.66	0.14	909.66	3	None
5	Pipe - (692)	39.00	36	Cir	24.686	907.63	910.09	9.965	909.66	912.12	0.14	912.12	4	None
6	Pipe - (691)	39.00	36	Cir	114.056	910.09	923.78	12.003	912.12	925.81	0.26	925.81	5	None
7	Pipe - (690)	39.00	36	Cir	22.781	923.78	926.54	12.115	925.81	928.57	0.26	928.57	6	None
8	Pipe - (689)	39.00	36	Cir	137.700	926.54	944.45	13.007	928.57	946.48	0.23	946.48	7	None
9	Pipe - (688)	39.00	36	Cir	12.655	944.45	945.09	5.057	946.48	947.12	0.28	947.12	8	None
10	Pipe - (687)	39.00	36	Cir	91.135	945.09	949.64	4.993	947.12	951.67	0.14	951.67	9	None
11	Pipe - (686)	39.00	36	Cir	51.266	949.64	952.21	5.013	951.67	954.24	0.16	954.24	10	None
12	Pipe - (685)	39.00	36	Cir	27.218	952.21	953.57	4.997	954.24	955.60	0.18	955.60	11	None
13	Pipe - (684)	39.00	36	Cir	18.424	953.57	965.00	62.038	955.60	967.03	0.91	967.03	12	Manhole

Church Q25 w Q25 MIP


Number of lines: 13

Run Date: 5/16/2018

NOTES: Return period = 25 Yrs. ; \*Surcharged (HGL above crown).



# Hillcrest Q10 MP




Project File: Existing 39in Hillcrest Q10 MP with Church Q10.stm

Number of lines: 3

Date: 5/16/2018

# Storm Sewer Profile

Proj. file: Existing 39in Hillcrest Q10 MP with Church Q10.stm




# Storm Sewer Summary Report

Line No.	Line ID	Flow rate (cfs)	Line Size (in)	Line shape	Line length (ft)	Invert EL Dn (ft)	Invert EL Up (ft)	Line Slope (%)	HGL Down (ft)	HGL Up (ft)	Minor loss (ft)	HGL Junct (ft)	Dns Line No.	Junction Type					
1	Pipe - (697)	137.3	36	Cir	226.620	890.21	895.54	2.352	893.20*	902.58*	0.88	903.46	End	Manhole					
2	Pipe - (695) (1) (1)	105.0	36	Cir	39.579	895.54	895.86	0.809	903.46*	904.30*	0.51	904.81	1	Manhole					
3	Pipe - (695) (1)	105.0	36	Cir	129.740	895.86	896.89	0.794	904.81*	907.55*	3.43	910.98	2	None					
Hillcrest Q10 MP										Number of lines: 3					Run Date: 5/16/2018				
NOTES: Return period = 10 Yrs. ; *Surcharged (HGL above crown).																			



# Church Q10 w Q10 MP




Project File: Church Q10 with 39in Q10 MP.stm

Number of lines: 13

Date: 5/16/2018

# Storm Sewer Profile

Proj. file: Church Q10 with 39in Q10 MP.stm



# Storm Sewer Summary Report

Line No.	Line ID	Flow rate (cfs)	Line Size (in)	Line shape	Line length (ft)	Invert EL Dn (ft)	Invert EL Up (ft)	Line Slope (%)	HGL Down (ft)	HGL Up (ft)	Minor loss (ft)	HGL Junct (ft)	Dns Line No.	Junction Type
1	Pipe - (697)	137.3	36	Cir	226.620	890.21	895.54	2.352	893.44*	899.51*	2.51	902.03	End	Manhole
2	Pipe - (695)	32.30	36	Cir	9.325	895.54	895.80	2.788	902.03*	902.05*	0.18	902.22	1	None
3	Pipe - (694)	32.30	36	Cir	28.513	895.80	897.28	5.191	902.22*	902.28*	0.17	902.45	2	None
4	Pipe - (693)	32.30	36	Cir	103.428	897.28	907.63	10.007	902.45	909.47	n/a	909.47 j	3	None
5	Pipe - (692)	32.30	36	Cir	24.686	907.63	910.09	9.965	909.47	911.93	0.12	911.93	4	None
6	Pipe - (691)	32.30	36	Cir	114.056	910.09	923.78	12.003	911.93	925.62	0.22	925.62	5	None
7	Pipe - (690)	32.30	36	Cir	22.781	923.78	926.54	12.115	925.62	928.38	0.22	928.38	6	None
8	Pipe - (689)	32.30	36	Cir	137.700	926.54	944.45	13.007	928.38	946.29	0.20	946.29	7	None
9	Pipe - (688)	32.30	36	Cir	12.655	944.45	945.09	5.057	946.29	946.93	0.24	946.93	8	None
10	Pipe - (687)	32.30	36	Cir	91.135	945.09	949.64	4.993	946.93	951.48	0.12	951.48	9	None
11	Pipe - (686)	32.30	36	Cir	51.266	949.64	952.21	5.013	951.48	954.05	0.13	954.05	10	None
12	Pipe - (685)	32.30	36	Cir	27.218	952.21	953.57	4.997	954.05	955.41	0.16	955.41	11	None
13	Pipe - (684)	32.30	36	Cir	18.424	953.57	965.00	62.038	955.41	966.84	0.78	966.84	12	Manhole

Church Q10 w Q10 MP Number of lines: 13 Run Date: 5/16/2018


NOTES: Return period = 10 Yrs. ; \*Surcharged (HGL above crown). ; j - Line contains hyd. jump.

The first part of the document discusses the importance of maintaining accurate records of all transactions. It emphasizes that every entry, no matter how small, should be recorded to ensure the integrity of the financial statements. This includes not only sales and purchases but also expenses and income. The document provides a detailed explanation of how to categorize these transactions correctly, ensuring they are recorded in the appropriate accounts. It also highlights the need for regular reconciliation to identify any discrepancies between the recorded amounts and the actual bank statements or receipts.

The second part of the document focuses on the preparation of the financial statements. It outlines the steps involved in calculating the net income, which is a key indicator of the company's profitability. This involves summing up all revenues and subtracting all expenses, including depreciation and amortization. The document also discusses the importance of providing a clear and concise explanation of the results, highlighting any significant changes or trends. It provides a template for the financial statements, ensuring that all required information is included and presented in a professional and easy-to-understand format.


The final part of the document addresses the issue of tax compliance. It explains the various taxes that may apply to the company's operations, such as income tax, sales tax, and property tax. It provides a detailed guide on how to calculate these taxes and how to file the necessary returns. The document also discusses the importance of staying up-to-date on the latest tax laws and regulations, as they can change frequently. It provides a checklist of the required documents and information for each tax filing, ensuring that the company is always prepared to meet its tax obligations.

# Existing 39" RCP\_Hillcrest Q25



# Storm Sewer Profile


Proj. file: Existing 39in Hillcrest Q25 with Church Q25.stm



# Storm Sewer Summary Report

Line No.	Line ID	Flow rate (cfs)	Line Size (in)	Line shape	Line length (ft)	Invert EL Dn (ft)	Invert EL Up (ft)	Line Slope (%)	HGL Down (ft)	HGL Up (ft)	Minor loss (ft)	HGL Junct (ft)	Dns Line No.	Junction Type	
1	Pipe - (697)	124.6	39	Cir	226.620	890.21	895.54	2.352	893.35	898.68	0.54	898.68	End	Manhole	
2	Pipe - (695) (1) (1)	85.59	39	Cir	39.579	895.54	895.86	0.809	898.68	899.00	0.25	899.25	1	Manhole	
3	Pipe - (695) (1)	85.59	39	Cir	129.740	895.86	896.89	0.794	899.25*	900.44*	1.65	902.10	2	None	
Existing 39" RCP_Hillcrest Q25										Number of lines: 3					Run Date: 5/16/2018
NOTES: Return period = 25 Yrs. ; *Surcharged (HGL above crown).															

# Church Q25 w/ Existing 39" RCP



Project File: Church Q25 with 39in RCP Downstream Connection.stm


Number of lines: 13

Date: 5/16/2018




# Storm Sewer Profile

Proj. file: Chuch Q25 with 39in RCP Downstream Connection.stm




# Storm Sewer Summary Report

Line No.	Line ID	Flow rate (cfs)	Line Size (in)	Line shape	Line length (ft)	Invert EL Dn (ft)	Invert EL Up (ft)	Line Slope (%)	HGL Down (ft)	HGL Up (ft)	Minor loss (ft)	HGL Junct (ft)	Dns Line No.	Junction Type
1	Pipe - (697)	124.6	39	Cir	226.620	890.21	895.54	2.352	893.17	898.68	2.11	898.68	End	Manhole
2	Pipe - (695)	39.00	36	Cir	9.325	895.54	895.80	2.788	898.68	898.70	0.27	898.96	1	None
3	Pipe - (694)	39.00	36	Cir	28.513	895.80	897.28	5.191	898.96	899.31	n/a	899.31 j	2	None
4	Pipe - (693)	39.00	36	Cir	103.428	897.28	907.63	10.007	899.31	909.66	0.14	909.66	3	None
5	Pipe - (692)	39.00	36	Cir	24.686	907.63	910.09	9.965	909.66	912.12	0.14	912.12	4	None
6	Pipe - (691)	39.00	36	Cir	114.056	910.09	923.78	12.003	912.12	925.81	0.26	925.81	5	None
7	Pipe - (690)	39.00	36	Cir	22.781	923.78	926.54	12.115	925.81	928.57	0.26	928.57	6	None
8	Pipe - (689)	39.00	36	Cir	137.700	926.54	944.45	13.007	928.57	946.48	0.23	946.48	7	None
9	Pipe - (688)	39.00	36	Cir	12.655	944.45	945.09	5.057	946.48	947.12	0.28	947.12	8	None
10	Pipe - (687)	39.00	36	Cir	91.135	945.09	949.64	4.993	947.12	951.67	0.14	951.67	9	None
11	Pipe - (686)	39.00	36	Cir	51.266	949.64	952.21	5.013	951.67	954.24	0.16	954.24	10	None
12	Pipe - (685)	39.00	36	Cir	27.218	952.21	953.57	4.997	954.24	955.60	0.18	955.60	11	None
13	Pipe - (684)	39.00	36	Cir	18.424	953.57	965.00	62.038	955.60	967.03	0.91	967.03	12	Manhole
Church Q25 w/ Existing 39" RCP													Number of lines: 13	
NOTES: Return period = 25 Yrs. ; j - Line contains hyd. jump.													Run Date: 5/16/2018	




# Existing 39" RCP\_Hillcrest Q10



# Storm Sewer Profile


Proj. file: Existing 39in Hillcrest Q10 with Church Q10.stm



# Storm Sewer Summary Report


Line No.	Line ID	Flow rate (cfs)	Line Size (in)	Line shape	Line length (ft)	Invert EL Dn (ft)	Invert EL Up (ft)	Line Slope (%)	HGL Down (ft)	HGL Up (ft)	Minor loss (ft)	HGL Junct (ft)	Dns Line No.	Junction Type
1	Pipe - (697)	103.3	39	Cir	226.620	890.21	895.54	2.352	893.35	898.58	0.38	898.58	End	Manhole
2	Pipe - (695) (1) (1)	71.00	39	Cir	39.579	895.54	895.86	0.809	898.58	898.53	0.22	898.53	1	Manhole
3	Pipe - (695) (1)	71.00	39	Cir	129.740	895.86	896.89	0.794	898.53	899.56	1.47	899.56	2	None
										Number of lines: 3		Run Date: 5/16/2018		
Existing 39" RCP_Hillcrest Q10 NOTES: Return period = 10 Yrs.														

# Church Q10 w/ Existing 39" RCP



# Storm Sewer Profile

Proj. file: Chuch Q10 with 39in RCP Downstream Connection.stm





# Storm Sewer Summary Report

Line No.	Line ID	Flow rate (cfs)	Line Size (in)	Line shape	Line length (ft)	Invert EL Dn (ft)	Invert EL Up (ft)	Line Slope (%)	HGL Down (ft)	HGL Up (ft)	Minor loss (ft)	HGL Junct (ft)	Dns Line No.	Junction Type		
1	Pipe - (697)	103.3	39	Cir	226.620	890.21	895.54	2.352	893.17	898.58	1.50	898.58	End	Manhole		
2	Pipe - (695)	32.30	36	Cir	9.325	895.54	895.80	2.788	898.58	898.57	0.19	898.77	1	None		
3	Pipe - (694)	32.30	36	Cir	28.513	895.80	897.28	5.191	898.77	899.12	n/a	899.12 j	2	None		
4	Pipe - (693)	32.30	36	Cir	103.428	897.28	907.63	10.007	899.12	909.47	0.12	909.47	3	None		
5	Pipe - (692)	32.30	36	Cir	24.686	907.63	910.09	9.965	909.47	911.93	0.12	911.93	4	None		
6	Pipe - (691)	32.30	36	Cir	114.056	910.09	923.78	12.003	911.93	925.62	0.22	925.62	5	None		
7	Pipe - (690)	32.30	36	Cir	22.781	923.78	926.54	12.115	925.62	928.38	0.22	928.38	6	None		
8	Pipe - (689)	32.30	36	Cir	137.700	926.54	944.45	13.007	928.38	946.29	0.20	946.29	7	None		
9	Pipe - (688)	32.30	36	Cir	12.655	944.45	945.09	5.057	946.29	946.93	0.24	946.93	8	None		
10	Pipe - (687)	32.30	36	Cir	91.135	945.09	949.64	4.993	946.93	951.48	0.12	951.48	9	None		
11	Pipe - (686)	32.30	36	Cir	51.266	949.64	952.21	5.013	951.48	954.05	0.13	954.05	10	None		
12	Pipe - (685)	32.30	36	Cir	27.218	952.21	953.57	4.997	954.05	955.41	0.16	955.41	11	None		
13	Pipe - (684)	32.30	36	Cir	18.424	953.57	965.00	62.038	955.41	966.84	0.78	966.84	12	Manhole		
Church Q10 w/ Existing 39" RCP										Number of lines: 13					Run Date: 5/16/2018	
NOTES: Return period = 10 Yrs. ; j - Line contains hyd. jump.																



## **APPENDIX B**

### **Hydrology Maps**


- 1. On-Site Hydrology Map**
- 2. City of Thousand Oaks Storm Drain System Master Plan**



HYDROLOGY AREA INFORMATION				
AREA NUMBER	AREA (Acres)	T.D.C. (Min.)	Q <sub>25</sub> (cfs)	Q <sub>10</sub> (cfs)
A1	4.32	5	8.60	7.13
B1 OFF	15.28	5	30.41	25.21

**HYDROLOGY INFORMATION**

LOCATION: THOUSAND OAKS  
 RAINFALL: 10.6"  
 PROJECT AREA: 4.32 ACRE  
 IMPERVIOUS AREA: 1.78 ACRE  
 SOIL NUMBER: 2  
 Q<sub>100</sub>=2.93 CFS/ACRE  
 Q<sub>25</sub>=1.99 CFS/ACRE  
 Q<sub>10</sub>=1.65 CFS/ACRE




**HYDROLOGY MAP**

CONEJO VALLEY CHURCH OF CHRIST  
 2525 E. HILLCREST DRIVE  
 THOUSAND OAKS, CALIFORNIA



**RJR ENGINEERING GROUP**  
 Planning Civil Engineering Flood Control/Hydrology  
 Geotechnical Engineering Geology Water Resources Environmental  
 3500 Camino Ave, Suite 200, Oxnard, CA 93030  
 (805) 485-3935 (805) 485-6496 FAX  
 E-mail: rjreng@rjreng.com

See Plate #2




See Plate #5

See Plate #7




**City of Thousand Oaks**  
**Storm Drain System Master Plan**  
 Hydrology Plate #6



- Legend**
- Hydrology Links
  - Subarea Boundaries
  - Street Centerline
  - City of Thousand Oaks Map Grid
  - Thousand Oaks City Boundary
  - 2001 - LIDAR 10 ft. Contours

Hidden Valley Wash (Lake Sherwood)  
 Watershed



October 2006





See Plate #8



**HYDROLOGY INFORMATION**

LOCATION: THOUSAND OAKS  
 RAINFALL: 10.6"  
 PROJECT AREA: 4.32 ACRE  
 IMPERVIOUS AREA: 1.78 ACRE  
 SOIL NUMBER: 2  
 Q<sub>100</sub>=2.93 CFS/ACRE  
 Q<sub>25</sub>=1.99 CFS/ACRE  
 Q<sub>10</sub>=1.65 CFS/ACRE

HYDROLOGY AREA INFORMATION				
AREA NUMBER	AREA (Acres)	T.O.C. (Min.)	Q <sub>25</sub> (cfs)	Q <sub>10</sub> (cfs)
A1	4.32	5	8.60	7.13
B1 OFF	15.28	5	30.41	25.21



REVIEWED FOR PERMIT ISSUANCE BY:  
CITY OF THOUSAND OAKS

DEVELOPMENT ENGINEER	DATE
PLANNING DIVISION	DATE
<TRAFFIC ENGINEER>	DATE
<BLDG. DIVISION - ADA COMPLIANCE>	DATE
<COSCA>	DATE

**CITY OF THOUSAND OAKS**  
**PUBLIC WORKS DEPARTMENT**

**HYDROLOGY MAP**

CONEJO VALLEY CHURCH OF CHRIST  
 2525 E. HILLCREST DRIVE

CITY OF THOUSAND OAKS DWG. NO. \_\_\_\_\_ SHEET \_\_\_\_ OF \_\_\_\_

811  
 Know what's below.  
 Call before you dig.

UNDERGROUND SERVICE ALERT OF SOUTHERN CALIFORNIA

DIAL TOLL FREE  
 8 1 1  
 AT LEAST TWO DAYS  
 BEFORE YOU DIG

REV.	SYMBOL	DESCRIPTION OF CHANGE	R.C.E.	DATE	P.D.E.	DATE

DESIGNED BY:  
RET 6/8/18  
DATE

DRAWN BY:  
RET 6/8/18  
DATE

CHECKED BY:  
RWA 6/8/18  
DATE

ENGINEER'S SEAL

PREPARED BY:

REGISTERED ENGINEER

C-58383  
RCE NUMBER